



Table of Contents

TITLE	PAGE
<i>Executive Summary</i>	1
<i>Project Summary</i>	2
Project Data	2
Project Location	2
Project Partners	2
Project Construction Material Budget	3
Project Work Force	3
Project Administration, Survey, Engineering, and Environmental Permits	3
<i>Introduction</i>	5
Site Description	6
Project Background	6
Project Design History	6
Phase I Pre-Design	7
CCA.60 Light Frame Construction Suspension Bridge	7
Final Project — Completed Timber Suspension Bridge	8
<i>Engineering Challenges to Overcome</i>	8
<i>Bridge Design Alternatives</i>	9
Center Pier Bridge	9
Simple Beam Bridge	9
Arch Bridge	10
Truss Bridge	10
Suspension Bridge Proves to be the Most Viable Solution	10
<i>Historical Significance of Suspension Bridges to the Appalachian Trail</i>	11
<i>USDA Forest Service's Use of Suspension Bridges</i>	13
<i>Suspension Bridge Nomenclature</i>	13
<i>Design Standards</i>	14
<i>Design and Construction of the Bridge Towers</i>	17
<i>Tower Installation</i>	18



TITLE	PAGE
<i>Foundation Design and Construction</i>	23
<i>Review of other Timber Tower Pedestrian Suspension Bridge Foundations</i>	24
<i>The Pochuck Quagmire Bridge “Snowshoe” Foundation.....</i>	28
<i>The “Snowshoe”</i>	34
<i>Backstay Anchorages</i>	35
<i>Helical Anchors — The Solution</i>	37
<i>Bridge Walkway-Stiffening Truss Railing Design and Construction</i>	39
<i>The Project “Comes Together”</i>	44
<i>Bridge Walkway Camber</i>	44
<i>Cable Saddles</i>	45
<i>Catenary Cable Geometry</i>	47
<i>Floodwater Clearance</i>	48
<i>Identifying the 100-Year Flood Level</i>	49
<i>The Main Cables — Catenary Cables.....</i>	50
<i>Spelter Sockets</i>	55
<i>Suspender Design and Installation</i>	58
<i>A Practical Lesson — “The Hard Way”</i>	63
<i>Aerial Bridge Assembly</i>	67
<i>Final Cable Tuning.....</i>	69
<i>Decking and Stairs.....</i>	70



TITLE	PAGE
<i>Field Modifications</i>	70
<i>Americans with Disabilities Act (ADA) Compliance</i>	71
<i>Environmental Integrity</i>	72
<i>Aesthetics</i>	72
<i>Project Supervision and Labor Force</i>	73
<i>Site Access</i>	74
<i>Public Safety, Worker Safety, and Project Partner Risk Management</i>	74
<i>Public Safety</i>	75
<i>User Education</i>	77
<i>Project Safety Plan — Worker Safety</i>	77
<i>Insurance</i>	79
<i>Project Engineering</i>	82
<i>Long-Term Maintenance</i>	83
<i>Project Value Accounting</i>	83
Material	84
Machine Time	84
Work-Hours	84
Project Construction Costs	84
<i>Summary of Construction Costs</i>	84
<i>Material & Equipment Cost Breakdown</i>	85
Foundation	85
Towers	85
Truss Bridge Walkway, Platform, and Stairs	86
Suspension System	86
Miscellaneous Material	86
Access Prep	86



TITLE	PAGE
Heavy Machinery for Tower and Bridge Construction	86
Hand Tools and Equipment	87
Miscellaneous	87
<i>Peoplepower Breakdown: Bridge-Specific Construction Only</i>	87
State Employees	87
Volunteers	88
<i>Peoplepower Breakdown Discussion</i>	88
<i>Project Cost Tabulation Exclusions</i>	88
<i>Preliminary Project Cost Estimates</i>	89
<i>Project Volunteers</i>	91
NY-NJ Trail Conference	91
GPU Energy	92
Saint Benedicts Prep School	92
Mountainview Correctional Facility	92
Assistance and Support	92
New Jersey Department of Environmental Protection	92
New Jersey Treasury Department - Division of Building and Construction	93
USDA Forest Service	93
Corporate Partners	93
<i>20-20 Hindsight</i>	93
<i>Conclusion</i>	94
<i>Appendices</i>	A-1 to H-2
<i>Plan Sheets</i>	Back of Publication



TITLE PAGE

Appendices

Appendix A — *Health and Safety Plan, Pochuck Bridge Construction Project* A-1 to A-8

Appendix B — *American Association of State Highway Transportation Officials (AASHTO) Guide Specifications* B-1 to B-4

Appendix C — *Materials List* C-1 to C-4

Appendix D — *Tools* D-1 to D-2

Appendix E — *Sources of Information on Material* E-1 to E-2

Appendix F — *References* F-1 to F-3

Appendix G — *Literature Listing* G-1

Appendix H — *Examples of Other Suspension Timber Bridges in the United States* H-1 to H-2



TITLE PAGE

List of Photos

Photo 1	The Appalachian Trail Pochuck Quagmire Bridge	1
Photo 1a	The Appalachian Trail Pochuck Quagmire Bridge	4
Photo 2	Installation of the west poles	20
Photo 3	Installation of the west poles	20
Photo 4	GPU Energy volunteers installing the tower cross-bracing on the west tower	20
Photo 5	GPU Energy volunteers installing the tower cross-bracing	20
Photo 6	GPU Energy volunteers installing the cross-braces and guylines	21
Photo 7	GPU Energy volunteers installing the cross-braces and guylines	21
Photo 8	GPU Energy volunteers installing the cross-braces and guylines	21
Photo 9	GPU Energy volunteers installing the cross-braces and guylines	21
Photo 10	View from the east tower looking at the west tower and Wawayanda Mountain during construction	22
Photo 11	Inclined towers of the Jackson River Bridge	24
Photo 12	Jackson River Bridge in the George Washington and Jefferson National Forest	25
Photo 13	The Lincoln Woods Trail Bridge	27
Photo 14	The Lincoln Woods Trail Bridge	27
Photo 15	The Lincoln Woods Trail Bridge	27
Photo 16	View looking through the east tower at west tower before foundation excavation	29
Photo 17	Same view as photo 16, but during foundation excavation. Note joist bracing and guylines	29
Photo 18	Bob Jonas and other volunteers excavating for the 12-foot by 16-foot “snowshoe” foundation	29
Photo 19	Wes Powers and Walt Palmer and others threading the #18 rebar through the base of the poles	30
Photo 20	Bituminous waterproofing, rebar, universal bands, the start of the snowshoe	30
Photo 21	Students from St. Benedicts Prep School and others	30
Photo 22	Crushed stone, 2-way rebar, and geogrid components	31
Photo 23	2-way #6 rebar is under the #18 rebar	31
Photo 24	Rebar was wired into place	31



TITLE	PAGE
Photo 25	Foolproof connection between the Chance® Helical Piers and rebar 32
Photo 26	“Bobkin” connection between Tensar® UX-1400 geogrid and perimeter #8 rebar 32
Photo 27	Judy Babcock of the NJ State Park Service installing the geogrid connection between tower and platform pole foundations 32
Photo 28	Charles McCurry of the NJ State Park Service checking that the vertical dowel bars were threaded through the universal band 32
Photo 29	Formwork was installed for the concrete pour 33
Photo 30	Crushed stone, helical piers, #18 rebar, 2-way #6 rebar, geogrid, #5 90-degree dowel bars, spikes, #3 rebar wrap, and project engineer 33
Photo 31	Foundation after concrete has set, but before backfill 34
Photo 32	East foundation before backfill 34
Photo 33	Tower pole and concrete collar connection. Note taper of concrete 35
Photo 34	Tibor Latincics holding one-half of the Chance® six helix square shaft screw anchor 37
Photo 35	Start of the helical anchor installation 38
Photo 36	Pete Morrissey directing the helical anchor installation by Trail Conference and GPU Energy volunteers 38
Photo 37	Drive rig, kelly bar adapter, and sheer pin torque indicator all in line 38
Photo 38	Helical anchors for the backstay anchorage were installed at 46 degrees 39
Photo 39	Pete Morrissey bolting the coupling between the two halves of the six helix anchor 39
Photo 40	Installation of the Chance® Helical Pier at each corner of the snowshoe foundation 39
Photo 41	The very first “rib” of the Truss walkway 42
Photo 42	Spaced chords were lined up with the spaced ribs 42
Photo 43	Ribs, alternating portals, and inclined outriggers make up the first section 42
Photo 44	Entire walkway truss frame was prefabricated at Wawayanda State Park 42
Photo 45	The east half of the bridge 43
Photo 46	Using a car jack to set the bridge to a 3.5 percent slope it would assume in the air in order to fit joints correctly 43
Photo 47	Bolts, lag screws, hurricane ties, and framing angles were used to make connections 43
Photo 48	Inclined outrigger supports 43
Photo 49	2-inch-by-6-inch joists atop the 6-inch by 6-inch stringers 43
Photo 50	Fabricated bridge sections were trucked to the site by the NJ Forest Fire Service 44
Photo 51	West tower - north pole cable saddle 45
Photo 52	Tibor Latincics and remains of the Hastings Trail Suspension Bridge 48
Photo 53	The timber towers were sheared at the base by floodwater driven debris 49



TITLE	PAGE
Photo 54	Hastings Bridge walkway remains flung downstream 49
Photo 55	The various connections between the wire rope - spelter socket - turnbuckles with eye and jaw-shackle - Chance® 1.75 ss rod 55
Photo 56	A terminal turnbuckle. Note the spelter socket connection to the eye at the top and the jaw-shackle connection to the Chance® Anchor at the bottom. 55
Photo 57	Wire rope clips on the Jackson River Bridge, GW & JNF in Virginia 57
Photo 58	Suspender connection on the PQB 60
Photo 59	Suspender connection on the Appalachian Trail Tye River Bridge 60
Photo 60	PQB CM Big Orange Piggyback Clip and flemish loop 61
Photo 61	Appalachian Trail Tye River Bridge Crosby Clip, chain shackle, and wire rope 61
Photo 62	Jackson River Bridge Crosby Clip, chain shackle, and swage socket 61
Photo 63	WMNF Lincoln Woods Trail Bridge clamp to rod suspender 61
Photo 64	Underside 3.5 percent bevel cut on the 6-inch by 6-inch cross-stringer set the walkway slope 62
Photo 65	Threaded rod through cross-stringer. Flat washer on top and bottom 62
Photo 66	Suspender assembly 62
Photo 67	Suspender assembly — top view 62
Photo 68	Suspender-stringer connection on Appalachian Trail Tye River Bridge, GW & JNF 63
Photo 69	U-bolt connection. Dry River Bridge, WMNF 63
Photo 70	Catenary cables and suspender assemblies ready to go 64
Photo 71	Twenty-one pairs of calculated suspenders 64
Photo 72	Trail conference volunteers preparing a bridge section for “lift off” 68
Photo 73	Hoisting up a bridge section with muscle power 68
Photo 74	Aligning the prepared joints 68
Photo 75	Tibor Latincics threading the suspender rod through a stringer 68
Photo 76	To reduce weight, bridge sections were joined without decking in place 68
Photo 77	Paul DeCoste, Greg Ludwig, and Alan Breach on the aerial assembly 68
Photo 78	Walkway structural skeleton before decking 69
Photo 79	Structural skeleton from underside prior to decking 69
Photo 80	Top view of bridge section connections 69
Photo 81	Underside of bridge section connections 69
Photo 82	Bridge prior to decking and stairs 70
Photo 83	Chris Mazza and other Trail Conference volunteers screwing down the walkway 2-inch by 6-inch decking 70
Photo 84	East side staircase construction 70
Photo 85	View of bridge looking east. Wawayanda Mountain is in the background 73
Photo 86	“Project Principals” 73
Photo 87	Project volunteers 92



TITLE **PAGE**

List of Figures

Figure 1	The Appalachian Trail map indicating the Pochuck Quagmire Bridge site	5
Figure 2	Sketch of suspension bridge components	15
Figure 3	West Tower, River view	19
Figure 4	Wild Oak Bridge Tower	25
Figure 5	Wallace Tract Bridge Pole Towers, George Washington and Jefferson National Forest	26
Figure 6	Simplified sketch of a typical foundation of the White Mountain National Forest suspension bridges	27
Figure 7	Helical anchor diagram	40
Figure 8	Cable saddle detail	45
Figure 9	Nomenclature for wire rope equations	50
Figure 10	The freebody diagram for the PQB tower poles	51
Figure 11	Typical wire rope components	52
Figure 12	Strand patterns	52
Figure 13	Attachment options for end of a wire rope	56
Figure 14	Wire rope clips	57
Figure 15	The correct way to attach wire rope clips	57
Figure 16	Cross-stringer suspender detail	59
Figure 17	Sketch of PQB in profile showing parabolic curve relationships	65
Figure 18	Symmetrical equal tangent parabolic curve mathematical relationship	65
Figure 19	Suspender length calculation example	66

List of Plan Sheets

TITLE **Plan Sheet**

Pochuck Quagmire Bridge, Profile View and Plan View	1
Walkway Cross Section A-A Detail and Walkway Truss Segment Detail	2
Handrail Detail, Stair Section C-C, and Stair Detail	3
West Tower, River View	4
Pole Footing Connection and Lower Chord Joint Detail	5
Cable Saddle Detail and Walkway Edge Detail	6
Primary Anchorage Power Installed Screw Anchor	7
Cross Stringer Suspender Detail	8



List of Acronyms

AASHTO	American Association of State and Highway Transportation Officials
AITC	American Institute of Timber Construction
ACI	American Concrete Institute
ADA	Americans with Disabilities Act
ATC	Appalachian Trail Conference
BOCA®	Building Officials and Code Administrators
CCA	Cromated Copper Arsenate
CY	Cubic yards
DBC	Division of Building and Construction
E	Modulus of Elasticity
EI IWRC RRL	Extra Improved Plow Steel, Independent Wire Rope Core, Right Regular Lay
FEMA	Federal Emergency Management Agency
GW & JNF	George Washington and Jefferson National Forest
KDAT	Kiln-dried after Preservative Treatment
KSI	Kips per Square Inch
MC	Moisture Content
MPH	Miles per Hour
NJDEP	New Jersey Department of Environmental Protection
NPS	National Park Service
OSHA	Occupational Safety Health Administration
PCF	Pounds per Cubic Foot
PFC	Pultruded Fiberglass Composite
PISA®	Power Installed Screw Anchors
PQB	Pochuck Quagmire Bridge
PSF	Pounds per Square Foot
PSI	Pounds per Square Inch
REA	Rural Electrification Administration
SYP	Southern Yellow Pine
TECO	Timber Engineering Company
USDA	United States Department of Agriculture
WIT	Wood In Transportation
WMNF	White Mountain National Forest